

John Karas - 14.54 acres

April 1926

The following described land in Virginia Military Survey # 3220 and being in Jefferson Township, Logan County, Ohio.

Beginning at a stake in the center of the Bellefontaine and Zanesfield Pike (known as Road # 10) said stake being the N.E. corner of a 23.36 acre tract now owned by Ed. Grubbs and said stake being 1.07 chains from the N.E. corner of a frame house on said Grubb's land; thence S. $1^{\circ} - 30'$ W. with the East line of said Grubb's tract 14.93 chains to a 2" iron pipe, thence N. $89^{\circ} - 52'$ E. 11.03 chains to an iron and large post, said iron and post being in the S.W. corner of an 8.00 acre tract now owned by Sarah C. Jones; thence with said Jones' east line N. $1^{\circ} - 28'$ E. 11.48 chains to a one inch iron pipe in the center of the Bellefontaine and Zanesfield pike, said iron being witnessed S. $37^{\circ} E.$ 1.11 chains to a 12" sugar, thence N. $72^{\circ} - 25'$ W. with the center of the Bellefontaine and Zanesfield Pike 11.47 chains to the place of beginning, containing 14.54 acres more or less as surveyed by F.F. Wright, April 10, 1926.

149 ID:1

BOOK 390 Page 55

INDEXED ON MAP

John Karas - 23.21 acres

The following described land in Virginia Military Survey # 3220 and being in Jefferson Township, Logan County, Ohio.

Beginning at a stake in the center of the Bellefontaine and Zanesfield Pike (known as road # 10) said stake being the N.E. corner of a 23.36 acre tract now owned by Ed. Grubbs and said stake being 1.07 chains from the N.E. corner of a frame house on said Grubbs' land; thence in a southerly direction with the East line of said Grubbs' tract 22.55 $\frac{1}{2}$ chains (passing a 2" iron pipe at 14.93 chains) to a small iron pipe and tall stump, said iron and stump being the N.W. corner of a 21.98 acre tract now owned by Wm. M. Jaques; thence in an easterly direction and with said Jaques north line 11.10 chains to a post; thence in a northerly direction 8.05 chains to an iron and a post, said iron and post being in the S.W. corner of an 8.00 acre tract now owned by Sarah C. Jones; thence with said Jones' East line; N.1°-28' E. 11.48 chains to a one inch iron pipe in the center of the Bellefontaine and Zanesfield Pike, said iron being witnessed S. 37° - E. 1.11 chains to a 12" sugar; thence N.72° - 25' W. with the center of the Bellefontaine and Zanesfield Pike 11.47 chains to the place of beginning, containing 23.21 acres more or less.

(149) 1D-2

INDEXED ON MAP


1926

Karas Land

The following described land in V.M.S. 3220 and being in Jefferson Township, Logan County, Ohio.

Beginning at an iron pin in the center of a road known as road # 55, said iron pin being at the N.E. corner of a 22.23 acre tract of land now owned by Wm.M.Jaques; thence North with the center of said road #55 to the S.E. corner of an 8.00 acre tract now owned by Sarah C.Jones, thence West with said Jones' South line to an iron and large post at the S.W. corner of said 8.00 acre tract, thence South 531.3 feet along the east line of a 23.21 acre tract now owned by B.F.Skidmore to a point in Wm. M.Jaques' North line, thence East along said Jaques' North line to the place of beginning, said tract containing 2.89 acres more or less.

INDEXED ON MAP



Karas Surrey N.M.S 3220
 Jefferson Tap.

(And B Found 3-14-33 See Book 513 Page 61)

A - Stake & of Pike Placed by Wright

B - I. Pipe & " " " " "

C { Iron Placed By Wright
 Large Post (149)

D Fence Post

E { Small I. Pipe Found. Note that this
 is same iron as marked C. page 21
 of this Book.

F Tall stump used for Post
 2" I. Pipe Placed by Wright.

Note bearings are given (when going
 around 14.54 Acres) to the left while
 angles were turned as shown.

I. Noted Line B.C. Produced toward D
 made a small angle as shown. Perhaps
 2 1/2 feet. Did not produce A.F. to E.
 Noted Fence on line A.F. very good for
 line.

All angles and distances shown
 were measured in field

clear Fine day
 Very Muddy
 Wright
 Mr. J. Karas

