

63

6<sup>th</sup> mo. June, 14<sup>th</sup> 1827. R Survey No 82  
 Surveyed for Solomon Coover Beginning at 2 bushes  
 2 lymns and ironwood in the east line of Walter  
 Dunsis survey No 9885 184 poles N 12 W from where  
 said line crosses the north line of Layton Gancy's  
 3221 - thence S 12 E 184 poles to 2 lymns a sugar tree  
 and large black walnut in Gancy's said line  
 thence with said line S 80 E (crossing a road at  
 40 poles, and 2 small branches, at 270 poles to a  
 stake in ~~the~~<sup>cross</sup> line of Gancy's Survey No 3220  
 a sugar tree and ash - thence S 26 E 210 poles  
 to a stake. - thence S 12 W 30 poles to the south  
 east corner of Henry Rector's land -  
 A mistake in the course called for in the deed, by which I  
 was surveying, being discovered in the 2 last lines - the survey was  
 not closed. J. M. Marmore  
 6/27

8257

Surveys No. 83, 84, &amp; 85

I James M. Marmore Surveyor of Logan County in  
 the State of Ohio, do certify, that under the provisions  
 of the Statute of the State of Ohio, entitled "an act  
 to enable the holders of land within this State to  
 perpetuate testimony relative to their lands," and  
 in pursuance of a notice given by Lyne Starting  
 as the administrator of Lucan Sullivan, deceased  
 and as the agent of the heirs of said Sullivan, dated  
 Jamesfield May 15<sup>th</sup> 1827, to Duncan McArthur,  
 Thomas Dickinson, Solomon Mays and Martin  
 Marmore, which notice is herewith returned marked  
 A. 808 also which said notice was published in  
 the Mad River Coerant, a paper printed in the  
 town of Nabana, agreeably to the requisitions of <sup>the</sup> said  
 Statute, which <sup>said</sup> paper was the nearest paper printed  
 to ~~the~~<sup>the</sup> lands described in said notice, proof of the  
 publication of which, together with a copy attached to



64 to the same is also herewith returned, marked A. & 29,  
I proceeded to make a resurvey of the surveys <sup>1803/1807</sup>  
of 1000 acres, <sup>1803/38</sup> of 780 acres, and <sup>1803/39</sup> of 1500  
acres, entered in the name of the representative of  
James Calderwood on Mad river as particularly  
described in said notices above referred to, and which  
two first described surveys were granted unto Lucas  
Sullivant, by patent bearing date the 19<sup>th</sup> day of  
March 1800, and the last survey was granted unto  
said Sullivant by patent bearing date the 15<sup>th</sup> day  
of March 1800, which three patents I had when  
making the said resurveys; beginning July 30<sup>th</sup>  
1827, being the day named in said notices, at the  
point represented on the plat herewith returned,  
(and following this certificate) by Zanis house, which  
place is referred to in the first part of John Story's  
deposition <sup>1801</sup> of the depositions taken by me, and  
herewith returned, marked B., and also the point  
where the deposition of James McPherson <sup>1802</sup> of  
said depositions, was taken, which point is in the  
now town of Zanesfield, and is about one pole  
south west from the house in which Dr. James Cline  
now lives, and is in the road from Upperman-  
-deshy to Urbana. — Thence <sup>1801</sup> to a stake  
at the point represented on said plat  
by the letter A near a red oak stump where the  
depositions of John Story <sup>1801</sup> and  
Ralph Knox <sup>1802</sup> of said depositions was taken  
from which said stake a beech about 15 inches in  
diameter ~~was~~ marked with the letters I S in two  
places, bears <sup>1801</sup> E 25 links, and also a beech marked  
with the letters M. B. & J. M. 1827 bears <sup>1801</sup> N 54  
links distant, which said place is on the north  
side of a hill where there are a number of old stumps  
around it, and near it is a sugar boiling place  
or camp. At the setting of this stake, at the place  
pointed out by the Story and Knox, and taking of  
said



65  
said depositions N<sup>o</sup> 1 & 2, were present, Thomas J. Bear-  
-thur, William Sullivan, Matthew Bonner, Daniel Butler,  
Noah J. McColloch, Solomon McColloch, Alexander Long, John  
Story, Ralph Knox, Benjamin Watkins, Jesse Garwood  
Thomas Stillwell, Benjamin S. Brown, Ferris Daugherty, and  
Robert McHarrison & Jeremiah Peasus chain carriers, and  
Benjamin Butler markers. I then ran the first course  
called for in survey N<sup>o</sup> 2237, allowing 30 minutes varia-  
-tion N<sup>75</sup> 30<sup>o</sup> E, passing at 5 poles a bush marked as fol-  
-lows, on its south side are 3 hacks made with a with  
a tomahawk, 22 inches and 4 inches apart, on the east-  
-ly side near the ground, are 4 hacks from 2 to 4 inches  
apart, 9 inches above the upper one of these is the  
first one of 3 more 2 and 5 inches apart, on the north  
side are 3 hacks all contained in 6 inches, on the ~~east~~<sup>west</sup>  
side are 3 hacks contained in 5 inches, among the hacks  
are the effigies of two persons sketched in the bark - South-  
-westerly from this about 2 poles stands another bush  
with a similar effigy all apparently old, and of  
the same age, crossing a branch at 62 poles, the road  
from Zanesfield to Urbana at 138 poles and old  
mill race at 188 poles, a spring branch at 192 poles  
a buckeye marked as a line tree at 234 poles (from  
which block A<sup>o</sup> 3 was taken in May 1826 which is  
here with returned) Mad River at 236 poles at the  
letter M as represented on said plat where the  
deposition of John Story N<sup>o</sup> 3 was taken a branch at  
332 poles <sup>410 poles</sup> to a sugar tree represented on said plat by  
the letter B. from which block A<sup>o</sup> 1 was taken in May  
1826, which is here with returned, which sugar tree  
before said block was cut out was marked on the  
eastly side with 3 marks in a line up the tree, a  
little more to the south were 2 marks, and on the  
south side were 5; after taking the block from the  
east side I discovered 2 hacks more on the northly  
side. - This tree stands in a bottom, with a very large  
elm ~~tree~~ tree fallen down against its south side



66. There is a good deal of timber lying down and rotting  
a round this tree. From which said tree a sugartree which  
I marked <sup>to day</sup> as a corner bears  $S 7^{\circ} E 32$  links, and a black  
walnut also cornered bears  $S 42^{\circ} E 35$  links. I thence  
run the second course of said survey allowing 1/2 minutes  
variation  $N 15^{\circ} 45' E 412$  poles, at 24 poles pass  $N 45^{\circ} W$  passing  
4 poles  $N 15^{\circ} W$  from a forked white walnut and 3 buckeyes  
north west corner to James McVitt's survey  $N 10^{\circ} 48' 75$  to  $4604$   
and south west corner to Duncan & Arthur's survey  $N 44^{\circ}$   
as represented on said plat. by the figure 8, cross-  
ing a branch at 50 poles, the road from Gainesfield to  
Chilford at 100 poles, a small drain at 184 poles, the  
road from Gainesfield to Farwoods mill at 255 poles a  
drain a little above its junction with another both of  
which have high steep banks at 228 poles, passing a  
few feet east of Thomas Dickinson's Spring at 278  
poles a drain or branch with high steep banks at  
314 poles a branch at 358 poles a drain at 384 poles  
to a large sugartree represented on said plat by the let-  
ter C, which sugartree had several blocks cut from  
it in May 1826, and which was marked before  
said blocks were taken from it, with 5 blocks one  
not through the bark and one of the two upper ones  
appeared older than the other, on the south side were  
3 blocks, one looks like a ball had been cut out lately  
with the corner of an ax on the north side 3 blocks  
scarcely through the bark; One of the blocks taken  
from this tree in May 1826 is also here with returned  
marked  $N 2$ ; near this sugartree on the wester  
ly side thereof is an elm log which appears to have  
fallen from near the top sugartree, and is much  
decayed, on the east side of this sugartree stand  
6 buckes marked as a corner, all of which have  
been blocked, from which sugartree a black bear  
marked J. W. M. 1827 bears  $N 24^{\circ} 170$  to  $W 14$  links.  
At this sugartree the deposition of said Knox was  
taken,  $N 4$  - I thence run the third course called  
for



67 for in said survey, allowing 30 minutes variation  
 N 83° 30' W 440 poles, crossing the Sugar camp branch  
 at 58 poles, at the letter X as represented on said plat  
 where I took the deposition of said Story & 7<sup>th</sup> cross-  
 ing Mad River at 104 poles, where I took the deposition  
 of said Story 706 at the letter C as represented on  
 said plat by the letter crossing it again at 160 poles  
 and again at 176 poles, the road from Sandusky  
 to Britana at 240 poles, a drain at 390 poles, to  
 a stake, from which a large elm marked W &  
 comes bears N 85° W 38 links, which stake is represen-  
 ted on said plat by the letter D, which stands on the  
 north side of a hill; at and around this place  
 there much fallen timber, and it is a very  
 thick place of bushes, and brush. — I thence  
 run the fourth course called for in said sur-  
 vey, allowing 45 variation) N 54° 15' W 412 poles, cross-  
 ing a branch at 46 poles, a head at 108 poles a  
 Spring branch at 186 poles a drain at 190 poles  
 one at 236 poles a road from Jamesfield to Hill  
 fountain at 246 poles, a branch at 266 poles, a  
 small Spring branch at 276 poles, another Spring  
 branch at 330 poles, another near its head at 366  
 poles, a small branch at 384 poles, to the point  
 A — Then returned to the said sugar tree  
 at the as before described and represented on  
 said plat by the letter B I then run the  
 second course called for in the survey N 83° 30' W  
 as described, in said notices allowing 30 min-  
 utes variation (So. 30° E 325 poles, passing a  
 buckeye at 32 poles marked as a live tree and  
 apparently old, on this direction of this line  
 about six feet to the west, crossing a Spring branch  
 at 152 poles, passing 3 elms northwesterly corner  
 to Thomas Parker's Survey N 44° 17' W as represented  
 on said plat by the figure 9 at 290 poles, to a large  
 fallen down ash; where the depositions of Solomon  
 McCallister



68 McCulloch, and Benjamin Watkins sr's were taken, near 68  
said ash stands a small hickory bush, which I marked as  
a corner, between which and the large fallen ash I  
caused a stone to be planted in presence of Benjamin  
Watkins, Solomon McCulloch, Noah J. McCulloch, Matthew,  
Bonner, Alexander Long, Jeremiah Reams, Robert M.  
Marron, Daniel Butler, and Benjamin Butler  
which stone is represented on said plat by the letter  
C, from which the said hickory bush bears  $N 50^{\circ} 15'$   
 $12$  links distant, a large bar oak (marked as a corner  
bears  $N 36^{\circ} 60$  links, an elm also marked as a corner  
bears  $S 72^{\circ} E$  18 links, all on the north side of a small  
pond. — I thence run the 3<sup>d</sup> course called for in  
said survey cr<sup>o</sup> 3138 allowing 30 minutes variation  
 $N 75^{\circ} 30'$  W 410 poles, passing a white oak and hic-  
-ory, corner to Parker's said survey, and corner to Wal-  
-ter Dunn's survey cr<sup>o</sup> 9592, 9618 & 10075, represented  
on said plat by the figure 8, at 68 poles, a mul-  
-berry tree, dogwood, and white oak, corner to Dunn's  
said survey and corner to James Denny's survey cr<sup>o</sup>  
4957 as represented on said plat by the figure 7 at  
158 poles, crossing Mad River at 248 poles, passing  
a black walnut at marked as a line at 310 poles  
represented on said plat by the letter D, on the west  
side of which walnut I caused a stone to be planted  
and took the deposition of Solomon McCulloch 1799  
crossing said road from Urbana to Sandusky at  $3\frac{1}{4}$   
poles, to a point represented on said plat by the letter  
G, when I took the deposition of said McCulloch 1799  
and caused a stone to be planted in the presence of  
Daniel Butler, Jervis Daugherty, Alex<sup>d</sup>. Long, Solomon  
McCulloch, Matthew Bonner, Noah J. McCulloch, Jeremiah  
Reams, Robert M. Marron, and Benjamin Butler;  
at and around this place, the timber is generally  
small, being low bushes and saplings, from this stone  
a small white oak bears  $N 75^{\circ} E$  24 links distant  
I thence run the last course of said survey allowing



30 minutes variation,  $r 8^{\circ} 36' N 323$  poles, passing  
Belms and bar oak, represented on said plat by the  
figure 6 at 64 poles, corner to Denny's said survey  
and southeasterly corner to John Galloway's survey  
no. 6449, crossing a branch at 112 poles, a spring branch  
at 130 poles, passing through the grave yard at the  
Baptists meeting house at 167 poles, passing the  
east end of Solomon Harp's house at 238 poles, cross-  
ing a small drain at 268 poles, to the said point A.

Then returned to the large sugar tree, as before described  
at the letter C, as represented on said plat. I thence  
run the second course called for in the survey no. 3139  
as described in said notices, allowing 30 minutes vari-  
ation  $r 74^{\circ} 30' E 65$  poles, crossing a small drain at 21 poles  
to the point H as represented on said plat, where I

marked 2 beeches as a corner - I thence run the 3<sup>rd</sup>  
course of said survey, allowing 30 minutes variation  
 $r 15^{\circ} 30' N 610$  poles, crossing a drain at 20 poles a  
branch at 68 poles, said sugar-camp branch at 158  
poles and at <sup>161 and at</sup> 171 poles, crossing the north line of  
David Bradford's survey no. 3136 and the south  
line of John Morris's survey no. 6121 at 242  
poles, 26 poles,  $r 58^{\circ} E$  from 2 sugar trees, represented  
on said plat by the figure 2, corner to the said  
surveys, crossing a small branch at 386 poles, at  
350 and at 370 poles, passing 2 beeches which I marked  
as a corner in the north line of Morris's said  
survey as represented on said plat by the figure  
3 at 424 poles, crossing the said road from Sandusky  
to Barbana at 460 poles a drain at 498 poles,  
one at 557 poles a branch at 568 poles, a drain  
at 595 to the point I as represented on said plat  
where I marked 2 beeches as a corner near a drain.

I thence run the fourth course called for in said  
survey  $r 74^{\circ} N 480$  poles, crossing a branch at 22 poles  
a drain just above a spring at 114 poles, a branch  
at the junction of a spring branch with that of 25



70 poles, a drain at 275 poles, Mad River at 296 poles a  
branch at 344 poles, a road at 352 poles, to the point  
as represented on said plat by the letter K, where I  
marked a beech and also with the letter M, and a sugar  
-tree as a corner and letter V, on the South side  
of a hill or bank — I thence run the 5<sup>th</sup> course  
called for in said survey allowing 30 minutes variation  
S 16° 30' E 400 poles, crossing a branch at 18 poles, ~~at~~  
52 poles entered into a deep drain, and continued up  
it 8 poles, and came out on the east bank again  
crossing the South line of Charles Spencer's survey  
no 5738 and North line of John Jalloway's survey  
no 6450 at 183 poles, 16 poles west from a road oak  
ash and by me, their corner as represented on said  
plat by the figure 5, crossing a drain at 244 poles  
to a stake represented on said plat by the letter  
L, from which said stake a small white oak mast  
as a corner and with the letter W bears S 83 1/2° W  
21 links, this point is in a thicket of hickory  
dog wood and other small bushes, where there is  
a good deal of old timber down, a good deal of  
which is rotten. — I thence run the last course  
called for in said survey, allowing 30 minutes  
variation N 74° 30' E 65 poles crossing, crossing a  
drain at 29 poles, to the place as before described  
at the letter D as represented on said plat. —  
And I then returned to the said point as be-  
fore described at the letter A, where I took Will-  
iam Asher's deposition no 11 and caused a  
stone to be planted, at the place of the stake,  
at the planting of which stone the following  
named persons were present, William Asher  
roak J. McColloch, Sr Matthew Bonner, Robert  
McMarmon, Jeremiah Reanus, and Benjamin  
Butler. — From the manner in which I made  
the survey which is represented on the said plat  
herewith returned, the point Jarvis's house as rep-  
resented



resented on said plat, will be very near in the centre of the survey no 3137 of 1000 acres as shown on said plat as now surveyed by me


Robert McErmont }  
Jeremiah Brown }  
Benjamin Butler master } James W. Marmon  
Surveyor of Logan County  
Surveyed July 30<sup>th</sup> & 31<sup>st</sup> Aug. 1 & 2 1827

I certify that the chain carriers were duly qualified as the law directs, before they entered on the duties of chain carriers in making the before described survey

James W. Marmon

INDEXED ON MAP  
8207 2D-9

18<sup>th</sup> Mo 15<sup>th</sup> 1827 Survey no 86  
Surveyed for Richmond Marmon, beginning at a hickory and sugar tree in the south line of James Mc Nutts survey no 4195 & 4604 at the south east corner to Martin Marmon's land; thence with Mc Nutts' said line N 69° E 80 poles (crossing a road at 48 poles, to a sugar tree and small by iron in said line; thence north 180 poles to a stone in the south line of Samuel Davis's survey no 3216 thence with said line S 2° E (one degree westerly variation) to a cypress and buckeye on the north bank of machine branch; thence with said branch S 50° W 28 poles to a stake in said branch; thence S 86° W 12 poles to a stake thence S 33° W 14 poles to a hackberry; thence S 86° W 34 poles to a sugar tree on the east side of a road leading and in the east line of a lot of land conveyed by Robert Marmon to Martin Marmon; thence with said line S 70° W 32 poles to a large rock south east corner to said lot of land; thence S 88° W 9 poles to a blue ash, buckeye and sugar tree, in the east line of another tract conveyed as aforesaid thence S 7° W 180 to the beginning containing 77 1/4 acres - 73 3/4 ac. out of James Mc Nutts' said survey & 4 1/2 off the N. corner of Samuel Davis's survey no 3216





186

Survey No. 674

Surveyed July 21st 1849

for Nathan Hockett to Herbert N. Norman  
 a lot of land as follows being part of Military  
 Survey No. 9889 on the waters of Mill Creek  
 beginning at the South East corner of said  
 survey at a stone (near a Buck stump called  
 for in the Original patent to Henry Massie)  
 thence  $N 10 \frac{3}{4}^{\circ} W 38 \frac{1}{2}$  poles to a stone in the  
 east line of said Survey and at the S. E.  
 corner to Samuel Deerduff's land, thence  
 $S 78 \frac{3}{4}^{\circ} W 16 \frac{3}{8}$  poles along the South line of  
 said Deerduff's land to a stone near  
 a steep bank of a branch of Mill Creek  
 thence  $S 10 \frac{3}{4}^{\circ} E 38 \frac{1}{2}$  poles to a stone near  
 a large Elm, thence  $N 78 \frac{3}{4}^{\circ} E 16 \frac{3}{8}$  poles to  
 the place of beginning containing Four  
 Acres

Samuel Deerduff  
 Peter Hantzman S. C.

INDEXED ON MAP  
 8207 3D

C. Hays Sur. L. Co. C.

Survey No. 675

July 23. 1849 Surveyed a lot

of land for Jeremiah Fisher as  
 follows being part of Military Survey No. 3137  
 on Mud river as follows beginning at a  
 stone on the north side of the Bellefontaine  
 and Franklinton Horse Turnpike and  
 at the S. E. corner of a lot deeded by C. Jones  
 and Wife to Jonathon Thomas in Sept. 1830.  
 thence  $N 32^{\circ} E 147$  poles to a stake in a meadow,  
 or, thence  $S 56^{\circ} E 24$  poles to a stake on the  
 West Bank of Mud river, thence  $S 42^{\circ} W$   
 $10 \frac{1}{2}$  poles to a stake in the North side of  
 the aforesaid road, thence  $N 67^{\circ} W 22 \frac{1}{10}$

8207

INDEXED ON MAP  
 8207 4D-1



187  
along the N. side of said Free Turnpike  
to the place of beginning, containing One  
Acre and  $132\frac{1}{2}$  perches.

Conrad Marshall  
Peter Pope S. C. C.

INDEXED ON MAP  
8207 4D-2

O. Hayes Sur. S. C. C.

8257  
Survey No. 676 July 23<sup>rd</sup> 1849 Surveyed  
for Jeremiah Fisher a  
part of Military Survey No. 3137 on Mad-  
river as follows Beginning at a stake at  
the S. W. corner of Isaac James and N. E.  
corner of C. James land, thence  $S 16^{\circ} 14' 50''$   
poles to a stone in an angle of Sac. Cross  
line, thence  $S 74\frac{1}{2}^{\circ} E 122\frac{1}{2}$  poles to a stake  
in another angle of S. Cross line, thence  
 $N 16^{\circ} E 40\frac{1}{5}$  poles to a stake in a township  
road and in S. James S. line; thence  
 $N 73^{\circ} W 121\frac{3}{5}$  poles along said James's south  
line to the place of beginning, containing  
 $30\frac{3}{4}$  Acres.

C. Marshall  
Jos. Collins S. C. C.

INDEXED ON MAP  
8207 5D

O. Hayes Sur. S. C. C.

Survey No. 677 July 23<sup>rd</sup> 1849 Surveyed a part of  
Military Survey No. 3222 on the waters  
of Madriver for Elder George S. Line as follows  
Beginning at a stake  $S 69\frac{1}{2}^{\circ} E 14\frac{3}{4}$  poles  
from Samuel Pope's S. W. corner, thence  
 $N 42\frac{3}{4}^{\circ} E 14\frac{3}{5}$  poles to a stone, thence  $S 32\frac{1}{4}^{\circ} E 18\frac{7}{5}$  sps.  
to a stone in the road leading from Pickerton  
to Bellefontaine, thence  $S 71\frac{1}{2}^{\circ} W 4$  poles to an-  
other stone in said road, thence  $N 67\frac{1}{2}^{\circ} W 17$   
poles to the beginning containing One Acre.

S. C. C.  
66

O. Hayes Sur. S. C. C.