


Lane Survey
V.M.S. 5092
Perry Township
December 16, 1978

Tract 1

The following described real estate situated in Perry Township, Logan County, Ohio and being part of Virginia Military Survey 5092 and more particularly described as follows:

Commencing at a stone in the center of County Highway No. 142 and in the north line of said V.M.S. 5092, said stone being station 203 + 06 as shown in Logan County Engineers field book No. 615, page 45; thence with the centerline of said C.H. 142 S.14°25'E. 17.2 feet to a railroad spike at the southwest corner of the West Mansfield Conservation Club's 8.73 acre tract, said spike being the beginning point of this description; thence with the south line of said 8.73 acre tract S.87°35'E. 381.0 feet to an iron pipe; thence S.5°17'W. 191.7 feet to an iron pipe; thence N.87°35'W. 313.4 feet to a railroad spike in the center of said C.H. 142; thence with said centerline N.14°25'W. 200.0 feet to the place of beginning.

Containing 1.53 acres more or less.




Lane Survey
V.M.S. 5092
Perry Township
December 16, 1978

Tract 2

The following described real estate situated in Perry Township,
Logan County, Ohio and being part of Virginia Military Survey 5092
and more particularly described as follows:

Commencing at a stone in the center of County Highway No. 142 and
in the north line of said V.M.S. 5092, said stone being station 203 + 06
as shown in Logan County Engineers field book No. 615, page 45; thence
with the centerline of said C.H. 142 S.14°25'E. 217.2 feet to a rail-
road spike, said spike being the beginning point of this description;
thence S.87°35'E. 313.4 feet to an iron pipe; thence S.5°17'W. 191.7 feet
to an iron pipe; thence N.87°35'W. 299.2 feet to a railroad spike in the
center of said C.H. 142; thence with said centerline N.8°42'E. 129.9 feet
to an iron bar; thence continuing with said centerline N.14°25'W. 65.2
feet to the place of beginning.

Containing 1.30 acres more or less.



Lane Survey
V.M.S. 5092
Perry Township
December 16, 1978

Tract 3

The following described real estate situated in Perry Township, Logan County, Ohio and being part of Virginia Military Survey 5092 and more particularly described as follows:

Commencing at a stone in the center of County Highway No. 142 and in the north line of said V.M.S. 5092, said stone being station 203 + 06 as shown in Logan County Engineers field book No. 615, page 45; thence with the centerline of said C.H. 142 S.14°25'E. 282.4 feet to an iron bar; thence continuing with said centerline S.8°42'W. 129.9 feet to a railroad spike, said spike being the beginning point of this description; thence S.87°35'E. 299.2 feet to an iron pipe; thence S.5°17'W. 65.7 feet to an iron pipe; thence S.52°43'W. 122.5 feet to an iron pipe; thence S.74°40'W. 236.7 feet to a railroad spike in the center of said C.H. 142; thence with said centerline N.8°42'E. 217.3 feet to the place of beginning.

Containing 1.10 acres more or less.

