


Survey No 538

8507



Surveyed June 13, 1845 for the trustees of Mary A Thurman the following tract of land, being Survey No 9371 & 12174, Beginning at B Beech corner to H Reyners land run N 72° W $78\frac{1}{2}$ poles to H Reyners N W corner then N $74^{\circ} 15'$ W 212 poles to a Black and Buckeye then N $53^{\circ} 45'$ E 220 poles to Hickory & 2 poplars passing Black walnut, B and Hackberry at 43 poles, Otter creek at 46 poles, Spring Branch at 208 poles, then S $35^{\circ} 50'$ E 172 poles to P, R O, & Sugar, then S $55^{\circ} 40'$ W 94 poles to Poplar & 2 Beech (one Beech down) then S 11° W 77.8 poles to the beginning containing $202\frac{27}{100}$ acres

At the same time divided said land as follows. Lot No 1. Beginning at Blue Oak & Buckeye run N $53^{\circ} 45'$ E 220 poles to Hickory & 2 Poplars (one Poplar gone, the other a dead stump) passing Black Walnut, B, & Hackberry at 43 poles Otter creek at 46 and Spring Branch at 208 poles, then S $35^{\circ} 50'$ E

83 poles to a Poplar Beech & Sugar then S
16° 50' W 141 poles to H Reymers & W corner
passing Otter creek at 45 poles then S 74°
15' W 212 poles to the Beginning Containing
152 ⁵⁰/₁₀₀ Acres

Lot No 2, Beginning at B Beech & E corner
to H Reymers land run S 72° W 78.5 poles to
H Reymers & E corner (marked on P) then
N 16 1/2° W 141 poles to a P, B, & Sugar then
S 35° 50' E 89 poles crossing Otter creek at
56 poles to Sugar, Red Oak, & Poplar then
S 53° 20' W 9.4 poles to a P & 2 Beech (one Beech
gone) then S 11° W 77.8 poles to the Beginning
Containing 49 ⁵⁰/₁₀₀ Acres A. A. Harrison
June 14 1845 C. S. G. C.



S B