

John W. Judge Engineering Company

CONSULTANT ENGINEERING

1201 EAST DAVID ROAD DAYTON, OHIO 45429

Description of Land to be Conveyed to


by Kenneth J. and Patricia Wright

Situate in Virginia Military Survey No. 9948, Richland Township, Logan County, Ohio and being more particularly described as follows:

Beginning at a concrete monument on the north right-of-way line of State Route 366 (Station 396+00, 30 feet right of the centerline);

thence from said place of beginning S 81° 18' 00" W with said north right-of-way line a distance of 24.62 feet to an axle at the south-east corner of the Ralph L. and Loretta H. Wisener tract as recorded in Volume 311, Page 557 of the Logan County Deed Records; thence leaving said right-of-way line N 7° 37' 50" W with the east line of the said Wisener tract and its extension a distance of 954.10 feet to an axle at the northeast corner of the Lottye B. Hord tract as recorded in Volume 339, Page 988 of the Logan County Deed Records; thence N 81° 30' 00" E a distance of 609.43 feet to an iron pin on the west line of the Doris M. Wickerham tract as recorded in Volume 230, Page 186 of the Logan County Deed Records; thence S 7° 31' 55" E with the west line of said Doris M. Wickerham tract a distance of 960.48 feet to an iron pin on the north right-of-way line of State Route 366 (30 feet north of the centerline); thence S 82° 08' 00" W with said north right-of-way line a distance of 583.10 feet to the place of beginning containing 13.371 acres, more or less, subject, however, to all legal highways and easements of record.

Deed Reference: Volume 339, Page 177



John W. Judge
February 11, 1975

5630 ID

INDEXED ON MAP