

# Lee Surveying and Mapping Co.



Farm Surveys • Lot Surveys • Topography • Subdivisions • Construction Layout

855 EAST SANDUSKY AVENUE  
BELLEFONTAINE, OHIO 43311

(513) 593-5780

CLAYTON M. LEE, P.S.  
JEFFREY I. LEE, P.S.

STANFIELD SURVEY

Lying in V.M.S. 10041, Rushcreek Township, Logan County, Ohio.

Being out of the southwest corner of that 20 acre tract in the name of Sara Betty Stanfield as deeded and described in Volume 394, Page 371, (Tract 1) of the Logan County Records of Deeds and being more particularly described as follows:

Beginning at a  $\frac{1}{2}$ " iron rod found marking the center-lines intersection of State Route 274 and Township Road 110.

THENCE, with the center-line of State Route 274, the following 3 bearings and distances:

N  $37^{\circ}$ -21'-45" E, 498.26 feet to a  $\frac{1}{2}$ " iron rod found.

N  $67^{\circ}$ -23'-09" E, 249.96 feet to a  $\frac{1}{2}$ " iron rod found.

N  $50^{\circ}$ -17'-12" E, 224.66 feet to a 'PK' nail set at the inter-section with the center-line of Township Road 137.

THENCE, with the center-line of said Township Road 137, the following 2 bearings and distances:

N  $87^{\circ}$ -11'-12" E, 54.95 feet to a railroad spike.

N  $53^{\circ}$ -24'-52" E, 25.32 feet to a railroad spike.

THENCE, with a fence line, the following 3 bearings and distances:

S  $35^{\circ}$ -12'-29" E, 292.22 feet to a  $\frac{5}{8}$ " iron rod set.

S  $60^{\circ}$ -11'-33" E, 136.61 feet to a  $\frac{5}{8}$ " iron rod set.

S  $1^{\circ}$ -55'-52" E, 305.93 feet to a  $\frac{5}{8}$ " iron rod set on the grantor's south property line.

THENCE, with said south property line, S  $86^{\circ}$ -58'-25" W, a distance of 1079.22 feet to a railroad spike found on the center-line of Township Road 110 marking the grantor's southwest corner.

THENCE, with the said center-line of Township Road 110, N  $2^{\circ}$ -43'-27" W, a distance of 15.95 feet to the point of beginning.


Containing 9.905 acres.

Prepared by:

*Clayton M. Lee*  
Clayton M. Lee  
Registered Professional Surveyor No. 6181  
April 16, 1986

This description prepared from an actual field survey.

INDEXED ON MAP  
2443 ID



L-1407  
ORIGINAL STAMP IN GREEN

