

Received 5-22-85 ok

Lee Surveying and Mapping Co.



Farm Surveys • Lot Surveys • Topography • Subdivisions • Construction Layout

855 EAST SANDUSKY AVENUE
BELLEFONTAINE, OHIO 43311

(513) 593-5780

CLAYTON M. LEE, P.S.
JEFFREY I. LEE, P.S.

TERRY LOVETT SURVEY

Lying in V.M.S. 3326, Rushcreek Township, Logan County, Ohio.

Being a part of that land lying in the name of Terry Lovett deeded and described in O.R. 1, Page 541 of the Logan County Records of Deeds and being better described as follows:

Beginning at a railroad spike set on the center-line of Township Road 126 being southerly along said center-line a distance of 560.7 feet from the southeast corner of Hertenstein's 40 acre tract, and northerly along said center-line a distance of 417.20 feet from the north line of the Joseph Cronkleton 51.379 acre tract.

THENCE, with the center-line of Township Road 126, S 5°-30' E, a distance of 30.00 feet to a railroad spike.

THENCE, S 84°-00' W, a distance of 1196.27 feet to a 5/8" iron rod set on a fence line.

THENCE, with said fence, S 8°-13'-20" E, a distance of 82.17 feet to a 5/8" iron rod.

THENCE, S 84°-40'-25" W, a distance of 623.10 feet to a 5/8" iron rod.

THENCE, N 5°-17'-50" W, a distance of 242.00 feet to a 5/8" iron rod set on a fence line.

THENCE, with said fence, N 84°-42'-10" E, a distance of 610.75 feet to a 5/8" iron rod set at a fence corner.

THENCE, with a fence, S 8°-13'-20" E, a distance of 129.81 feet to a 5/8" iron rod.

THENCE, parallel to and 30.00 feet ^{Northerly} ~~southerly~~ from the second called line of this survey, N 84°-00' E, a distance of 1197.70 feet to the point of beginning.

Containing 4.249 acres.

Prepared by:


Clayton M. Lee

Clayton M. Lee

Registered Surveyor No. 6181

May 21, 1985

This description prepared from an actual field survey.



ORIGINAL STAMP IN GREEN