

Lee Surveying and Mapping Co.



CLAYTON M. LEE, P.S.
JEFFREY I. LEE, P.S.

855 East Sandusky Avenue
Bellefontaine, Ohio 43311
Phone 593-5780



Farm Surveys • Lot Surveys • Topography • Subdivisions • Construction Layout

BOOGHER 0.918 ACRE SURVEY

Lying in the northwest quarter of the northwest quarter of Section 19, T-6, R-8, Stokes Township, Logan County, Ohio.

Being out of that Alan Boogher 40.432 acres (New survey of said northwest quarter of the northwest quarter of Section 19) and being more particularly described as follows:

Beginning at a railroad spike set on the center-line of County Road 17, also being on the west line of Section 19 and the west line of Logan County. This point lying S 1°-32' W, along said section line a distance of 870.70 feet from the northwest corner of said Section 19.

THENCE, at right angles to said section line, S 88°-28' E, a distance of 200.00 feet to a 5/8" iron rod, passing an iron rod at 25.00 feet.

THENCE, parallel to the west section line, S 1°-32' W, a distance of 200.00 feet to a 5/8" iron rod.


THENCE, N 88°-28' W, a distance of 200.00 feet to a railroad spike set on the west section line, in the center-line of County Road 17, passing an iron rod at 175.00 feet.

THENCE, with said center line, N 1°-32' E, a distance of 200.00 feet to the point of beginning.

Containing 0.918 acre (40,000 square feet).

Previous deed reference: Volume _____, Page _____.

Prepared by:


Clayton M. Lee
Registered Surveyor No. 6181
January 2, 1985



ORIGINAL STAMP IN GREEN

7289 1D-1

INDEXED ON MAP

L-1220-4

Lee Surveying and Mapping Co.



CLAYTON M. LEE, P.S.
JEFFREY I. LEE, P.S.

855 East Sandusky Avenue
Bellefontaine, Ohio 43311
Phone 593-5780



Farm Surveys • Lot Surveys • Topography • Subdivisions • Construction Layout

BOOGHER 40.432 ACRES

Lying in Section 19, T-6, R-8, Stokes Township, Logan County, Ohio.

Being the northwest quarter of the northwest quarter of said Section 19 as determined by a new survey of said section, with the boundary of said northwest quarter of the northwest quarter more particularly described as follows:

Beginning at a 1" square iron bar found marking the northwest corner of said Section 19 and being at the center-lines inter-section of County Road 17 and County Road 88.

THENCE, with the north line of Section 19 (center-line of County Road 88), S 88°-33'-50" E, a distance of 1324.82 feet to a railroad spike.

THENCE, S 1°-26'-40" W, a distance of 1327.88 feet to a 5/8" iron rod, passing an iron rod set at 25.00 feet.

THENCE, N 88°-36'-20" W, a distance of 1326.88 feet to a railroad spike set on the center-line of County Road 17 (West section line), passing an iron rod set at 1301.88 feet.

THENCE, with said center-line and section line, N 1°-32' E, a distance of 1328.83 feet to the point of beginning.

Containing 40.432 acres.

Previous deed reference: Volume _____, Page _____.

Prepared by:



Clayton M. Lee
Clayton M. Lee
Registered Surveyor No. 6181
January 2, 1985

7289 1D-2

ORIGINAL STAMP IN GREEN

INDEXED ON MAP

WEST SIDE OF SEC. 19 = 5315.32'

1328.83' SET RR SPIKES 870.70' CO. RD. 17
1328.83' SET RR SPIKES 870.70' CO. RD. 17
258.13' N 1°-32'E

SEC. 19, T-6, R-8

SEC. 18

NORTH SIDE OF SEC. 19 = 5299.26'

S 88°-33'-50" E
1324.82'

CO. RD. 88

FOUND HARBOR TOOTH 1.05' N & 0.4' W. OF TRUE COR.
SET RR SPIKE (STRINGTOWN PIKE)

SEC. 19

(3 A. ±)

SET 5/8" IRON ROD

FOUND STONE @ NE SEC. COR.

40.432 AC.
- 0.918 AC
= 39.514 AC. REMAINING

CREED

S 1°-26'-40" W

1327.88'

FLAGGED THIS LINE



SCALE = 1" = 200'

EAST SIDE OF SEC. 19 = 5300.1'

S 1°-10'-50" W TWP. RD. 86

S 88°-28' E
200.00'
40,000
= 0.918 AC.
S 1°-32' W
200.00'
N 88°-28' W
200.00'

SET 5/8" IRON ROD

SET 5/8" IRON ROD

SET RR SPIKE

N 88°-36'-20" W
1326.88'

SET 5/8" IRON ROD

ALAN BOOGER

SURVEY OF THE NORTHWEST QUARTER OF THE NORTHWEST QUARTER OF SEC. 19, T-6, R-8 STOKES TWP, LOGAN CO, OHIO PLUS SURVEY OF 0.918 ACRE OUT



By: *Jeffrey Lee*

JEFFREY E. LEE
REG. SURVEYOR 6359

7289 1P

INDEXED ON MAP

SOUTH SIDE OF SEC. 19 = 5331.96'

ORIGINAL STAMP IN GREEN

N 88°-43'-40" W

FOUND STONE @ SW COR. SEC. 19
CO. RD. 87

AUGLAIZE CO.

LOGAN CO.