

Feb. 25, 1918

Survey of a part of the north half
of the N.W. quarter of S. 18 T. 4 R. 14.
Union Twp.

A- N.W. corner of section
18" W.O. N. 48 W. 56 lks.
22" W.O. N. 69 E 51 lks.

A.B. S. 70 Poles.

B. Stake

B.C. E. 23 Poles

C. Stake

C.D. S. 10 Poles

D. Stake


D.E. E. 59 Poles

E 10" White Elm S. 21 E. 1 1/2 lks.
Burr Oak N. 53 W. 27 lks.

E.F. S. 2 1/2 poles.

From notes of survey
Feb. 9, 1887. by
Jo. W. Marmay
C.S.

10.11
16.1.6



INDEXED ON MAP

2197

F Stake

F.G. E 80 Poles.

G Stake

G.H. N 1 1/2 E 82 Poles.

H - N.W. corner of Q. 5
15" W.O. N. 9 W. 112 lks.
17" W.O. N. 7 1/2 E. 104 lks.

H.H. N 119 1/2 of section 164 Poles

Start of an anchor post taken
for the N.E. corner of the S.W.
quarter of S. 12 T. 4 R. 14

Run S. $6\frac{3}{4}$ W. 20.38 chs. to
post.

Run along south fence N. $16\frac{1}{2}$ W.
29.27 chs. to center of
Carlisle pipe.

There is a small angle in fence
line to right at the pipe.

Thence along the Carlisle Pipe
N. $44\frac{1}{2}$ E. 22.63 chains to
center of a road to west.
Back bearing S. $44\frac{1}{2}$ W.

Run along fence line for mark
line of section S. 96 E. 13.00 chs.
Chained along N line of

Section from anchor post at
N.E. corner of longfield
40.41 chs. and found stone at
section corner.